



MEMORANDUM

TO: MARINUS LINK PTY LTD
FROM: HAYDEN BURGE
SUBJECT: MARINUS LINK - STAGING REVIEW
DATE: 26/06/2024
CC: N/A

INTRODUCTION

Landform Architects prepared the Landscape and Visual Impact Assessment (LVIA) as part of the Environment Effects Statement under the Environment Effects Act 1978 (Vic) and the draft Environmental Impact Statement under the Environment Protection and Biodiversity Conservation Act 1999 (Cth) (the EIS/EES). This memorandum should be read in conjunction with LVIA that is technical appendix R of the EIS/EES exhibited May 2024.

The LVIA was prepared assuming the Project would be constructed across two stages commencing 2025 with final rehabilitation being completed in 2030.

- Stage 1 will include earthworks and site preparation of the converter station site to address requirements for both converter stations, access tracks and construction laydown areas, and all HDD drilling for the shore crossings, road and river crossings for both Stages, and trenching works to install conduits and joint pits within the linear easements that will accommodate cables for both Stages. Stage 1 includes laying the cables for the Stage 1 cable circuit (including across Bass Strait), and construction of the Stage 1 converter station at each of Hazelwood and Heybridge (and transition station, if required). Rehabilitation works would be implemented following Stage 1 works; and
- Stage 2 will include installing the cables for the Stage 2 cable circuit (including across Bass Strait) and construction of the converter stations at Hazelwood and Heybridge. Final reinstatement would occur following the completion of Stage 2 activities.

The EIS/EES assumed the stage 2 cable would be installed immediately after the Stage 1 cable was completed. The EES/EIS was prepared considering the construction of both stages would be from 2025-2030.



MLPL is seeking approvals for both Stages, but the timing for delivery of Stage 2 will be subject to market demand. Stage 1 would be completed, with testing and commissioning by 2030 as anticipated. The proposed amendment is related to Stage 2, which is proposed to be laid and commissioned by 2033.

Further detail on the proposed change is set out in *Marinus Link Information Update #1 – timing of Stage 2* available on the Marinus Link website ([Marinus Link Information Update #1 – timing of Stage 2 Marinus Link](#)) and the instructions provided for this supplementary assessment (Attachment 1).

LVIA - CONSTRUCTION IMPACTS

The LVIA considered the Project's visual impacts during construction, which is the subject of this proposed change, and the operation of the Project. The key activities and considerations for construction are set-out in Section 3.1 of the LVIA. The Project's visual impact was assessed through 17 land-based locations between the Victorian shore crossing at Waratah Bay and the convertor station at Hazelwood.

The LVIA determined that the overall visual impacts of construction activities will be noticeable due to the close proximity of the works. Views will be short in duration and extent. The impacts on views and amenity will be high, albeit temporary. There were no EPR's considered relevant to mitigate the Projects visual impacts during construction.

CHANGES TO THE ASSESSMENT

Although the proposed change sought by this amendment may result in increased timeframes for construction, there would not be a material change in the overall level of assessed visual impacts.

Construction works would be relatively short in duration in any one area and temporary only. The proposed route would not alter. Therefore, most of the above-ground infrastructure will still be located in farming areas, which has a low sensitivity to changes in views or the landscape. The project route and key project infrastructure still avoids sensitive landscapes and areas of National Park or State Forests. In sensitive areas, vegetation removal and ground disturbance have been avoided through HDD.

Following construction, all redundant infrastructure, tracks, fencing and hardstands will be removed and rehabilitated.

Based on the above, there appears to be no need to alter the EPR's as set out in the LVIA.

ATTACHMENTS

Attachment 1 - Marinus Link supplementary impact assessment - revised timing of stage 2

Marinus Link supplementary impact assessment - revised timing of stage 2

1. BACKGROUND

Marinus Link Pty Ltd (MLPL) have proposed a change to the timing of the two stages of the Marinus Link project (the project) that is different to what has been assessed in the EIS/EES. Each stage would deliver one complete 750 MW HVDC circuit between Tasmania and Victoria.

The EIS/EES assumed the stage 2 cable would be installed immediately after the stage 1 cable was completed, and this would occur between 2025 and 2030. [REDACTED]

[REDACTED] The EIS/EES and technical reports note that the timing of stage 2 will be subject to market demand.

MLPL recently published on their website an information update regarding the timing of delivery of stage 1 and stage 2. A copy of this information update, titled *Marinus Link Information Update #1 – timing of Stage 2*, is available here: [EIS/EES updates Marinus Link](#). This information is summarised below, but all specialists are requested to read the information provided on the MLPL website.

MLPL is now seeking supplementary impact assessments from technical specialists to consider whether the change in staging timing presents any changes to the impact assessment/s completed to support the EIS/EES.

The purpose of this document is to:

- provide further description of the activities and timeframe associated with the revised timing of stage 2.
- outline the scope of the supplementary assessment required of potential impacts associated with the revised timing.

2. PROJECT DESCRIPTION

The following section provides a summary of the *Information Update #1* provided on the MLPL website, with some further description of the works proposed to be completed in stage 1 and stage 2, and the timing of stage 2.

2.1 PROJECT CONSTRUCTION ACTIVITIES

The type of equipment used, and the nature of the works would be same as those outlined in the Project Description which has informed your technical assessment for the EIS/EES.

2.1.1 Stage 1

Stage 1 will include the works as assessed in the EIS/EES:

- Earthworks and site preparation for:
 - the converter station site to address requirements for both converter stations for stage 1 and stage 2.
 - access tracks and construction laydown areas.
 - all HDD drilling for the shore crossings, road, rail, third party asset, vegetation and river crossings for both stages.
 - trenching works to install conduits and joint pits within the linear easements that will accommodate cables for both stages.
 - sea floor pre-lay grapnel run.
- Laying the cable for stage 1 across Bass Strait and along the land cable route.
- Construction of the stage 1 converter station at Hazelwood, communications building (and transition station, if required).
- Establishing major construction laydown areas and access tracks, which will remain in place through the interim period between stage 1 and stage 2.

Fences will be removed along the construction area after completion of temporary reinstatement following completion of stage 1 and land use would be able to resume. It is anticipated that the haul road along the construction corridor will also be removed at the completion of stage 1 [REDACTED].

Stage 1 works on each property will include temporary reinstatement works. This will include including temporary infrastructure necessary to comply with Property Management Plans and to facilitate efficient use of the land in the interim period prior to stage 2 works.

Stage 1 will be completed when temporary reinstatement works are completed on each property. Rehabilitation works will be done following completion of stage 1 works.

2.1.2 Stage 2

Stage 2 works will include:


- Accessing and opening joint pits (requires removing soil and storing topsoil to reinstate) to enable cable pulling between joint pits. It is assumed there will be no ground disturbance along the cable route between joint pits.
- Accessing and establishing construction areas either side of conduits (that were constructed by trenchless construction methods in stage 1) under road, rail, third party assets, vegetation, river crossings and the shore crossing.
- Delivering cable drums that will be stored at major laydown areas in stage 2, in the same manner as stage 1, then transporting drums to joint pits for installation.
- Preparing the seafloor for stage 2 with a pre-lay grapnel run, then laying the subsea cables in the same manner as stage 1.
- Laying the cable for stage 2 across Bass Strait and along the land cable route.
- Delivering the transformer to the converter station site.
- Installing (including below-ground foundations) and commissioning the second converter station.
- Final reinstatement work following completion of stage 2.

2.2 TIMING

Stage 1 will take place between 2025 and 2030. Consistent with the EIS/EES, properties along the cable alignment will host main construction works for a period of time within that overall 5 year period. The stage 1 circuit will be commissioned by 2030.

Stage 1 works will be completed in 2030 and stage 2 works will commence in 2031.

Stage 2 circuit will be laid and commissioned by 2033.



3. SCOPE OF SUPPLEMENTARY ASSESSMENT

Based on the above, Tetra Tech Coffey (on behalf of MLPL) is now seeking an assessment, supplementary to your technical impact assessment prepared to support the EIS/EES, to consider the changes in project staging.

Your assessment should address the following key questions:

1. Identify whether a change to the timing for delivery of the works for stage 1 and stage 2 in accordance with the MLPL *Information Update #1* and project description information in this document would have any material implications for the assessment or conclusions of your technical assessment report (report) published with the EIS/EES and result in:
 - a. any additional impacts to those identified in your report
 - b. any changes to impacts identified in your report
 - c. any changes to the conclusions set out in your report.
2. Identify whether, as a consequence of the changed timing for delivery of stage 2 and associated works there are:
 - a. Any mitigation measures or Environmental Performance Requirements would be recommended in addition to those set out in your report
 - b. Any changes to any mitigation measures and Environmental Performance Requirements set out in your Report would be recommended.

Your assessment must be documented in a short report/letter as a supplement to the report that you have already prepared and is published with the EIS/EES. The supplementary report/letter must be concise, document your assumptions and draw on the methods and information already documented in your report for the EIS/EES. If you make any additional assumptions to inform your supplementary report/letter these must be documented in the report/letter.

It is expected that the reports/letters will be quite short. The supplementary report/letter will be published as an information update to the EIS/EES and made available to the public on the Marinus Link website here:

[EIS/EES updates Marinus Link](#).



[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]